


Sl. No	Description of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications, Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Cum	38.28	1900.00	
2	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air, to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications	Sqm	255.20	18.00	
3	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	255.20	33.00	
4	Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications	Sqm	255.20	20.00	
5	Supplying, placing & compacting ready made cold bituminous pothole patching mix in accordance with IRC 116-2014 in 50 kg plastic sturdy bags. The mix shall contain at least 5.6% MC 800 cutback Bitumen & suitable anti-stripping agent. The mix shall be workable for at least 6 months.	Cum	315.00	333.00	

D. V. J. R.

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-76.

6	Supply of the Labour Heavy Mazdoor to the required place as per the direction of the engineer in charge Complete as per Specification, and as per direction of Engineer-in charge	Day	459.00	450.00
7	Tractor 50 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work	Day	48.00	2200.00
8	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	405.36	130.00
9	Removing Precast slab of drain and stacking with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Sqm	1013.40	100.00
10	Refixing precast slabs of drains and pointing in CM 1:3 etc complete	Sqm	1013.40	100.00
11	Cost of Haulage Excluding Loading and Unloading MORTH -100/ Chapter 1 Case-I : Surface Road ITEM no. 17.4 , KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (15 KM lead taken	Cum	405.36	90.00


Signature of Contractor


EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.